



Sacramento
Area Flood
Control
Agency

ADDENDUM NO. 2

CONTRACT NO. 4099

For


NATOMAS LEVEE IMPROVEMENT PROGRAM

**Borrow Site Leveling, Reclamation, and Grassland Establishment
Project**

Date: May 27, 2011

APPROVED BY: SACRAMENTO AREA FLOOD CONTROL AGENCY


Richard M. Johnson
Executive Director


Date

TO ALL PROSPECTIVE BIDDERS:

All prospective bidders are hereby advised that this addendum includes amendments to the Contract Documents that were issued by the Sacramento Area Flood Control Agency on April 28, 2011. The bidders are to review all of the amendments listed herein, and acknowledge receipt of this addendum in the appropriate section of the Bid Form.

Office 916-874-7606
Fax 916-874-8289

1007 - 7th Street, 7th Floor
Sacramento, CA 95814-3407



CLARIFICATION

For the purpose of bidding on this contract, bidders shall assume the following:

1. The levee contractor is required to grade the airport borrow sites to a tolerance of +/- 2.0-inches to the finished sub-grades shown on their contract documents.
2. Once their grading is complete, an as-built survey will be performed in order to obtain final approval from the Agency.
3. The levee contractor will then uniformly spread topsoil over the sub-grade.
4. Assume the levee contractor will spread the topsoil to a final tolerance of +/- 3.0-inches.

AMENDMENTS TO CONTRACT DOCUMENTS

PART III – TECHNICAL SPECIFICATIONS

Section 31 22 19 Precision Site Leveling

PART 3 – EXECUTION

3.05 FIELD QUALITY CONTROL

DELETE:

B. GRADE AND CROSS SECTION: Surveys to verify that the dimensions, slopes, lines and grades, maximum clod size, and tolerance limits conform to those shown on the Plans. A post-leveling survey report shall be provided to the Agency for review and approval.

REPLACE WITH:

B. GRADE AND CROSS SECTION: Surveys to verify that the dimensions, slopes, lines and grades, maximum clod size, and tolerance limits conform to those shown on the Plans. Pre and post leveling surveys shall be by means and methods adequate to determine contract quantities, and to ensure that sites are graded to drain to the slopes indicated on the project Plans. A post-leveling survey report shall be provided to the Agency for review and approval.